

# AMERICAN EMBASSY

FACILITY MAINTENANCE SECTION

P.O.BOX.26431, MANAMA, BAHRAIN

TEL: 17242877, FAX: 17232391

## FACSIMILE TRANSMITTAL SHEET

**Subject: Supply, installation and commissioning of DX units (R-410A)**

Total Pages: 1

US Embassy requires professional services with respect to supply, installation and commissioning of Air conditioning units. You are requested to submit a quotation of the bellow items:

| Item no. | Description  | quantity |
|----------|--|----------|
| 1        | Split AC unit 18,000 BTU (1.5Ton) rated for high Ambient temperature | 28       |
| 2        | Split AC unit 30,000 BTU (2.5Ton) rated for high Ambient temperature | 1        |
| 3        | Split AC unit 24,000 BTU (2Ton) rated for high Ambient temperature   | 4        |

| Item no. | Description   | quantity |
|----------|---|----------|
| 1        | Split AC unit 36,000 BTU (3Ton) rated for high Ambient temperature            | 3        |
| 2        | Split AC unit 48,000 BTU (4Ton) rated for high Ambient temperature            | 2        |
| 3        | Split AC unit 60,000 BTU (5Ton) rated for high Ambient temperature            | 1        |
| 4        | Package AC unit 60,000 BTU (5Ton) rated for high Ambient temperature          | 1        |
| 5        | Package AC unit 150,000 BTU (12.5Ton) rated for high Ambient temperature      | 3        |
| 6        | Package AC unit 120,000 BTU (10Ton) rated for high Ambient temperature        | 1        |
| 7        | Portable outdoor AC 36,000 unit BTU (3Ton) rated for high Ambient temperature | 2        |

Please submit two individual quotations for both below and above 3Ton units. The scope of work should include removal of existing AC units. Please note that all coil units should be weather proof coated. Spilt A/C units should be supplied with 5 meter long pipes included in the price and all refrigerant pipes should be rated for high pressure R-410A system - i.e. Mueller USA. All extra pipe length required should be measured by the contractor during the site visit. Package A/C units replacements should includes all related modification may required i.e. ducting, wiring, controls...etc.