

EMBASSY CONCRETE FENCE RE-COATING SCOPE OF WORK

To be re-coated the concrete part of the US Embassy existing perimeter fence. Total square footage for re-coating is approximately 2050 square meter including both sides and upper surface of the fence concrete part. For doing that, please keep to the following:

1. Scrape and clean all areas of the fence concrete where there are flakes and peelings of the old plaster, in order to have firm and sound basis before re-coating starting;
2. Patch up the existing plaster with the material having similar qualities as the existing one; keep to the manufacturer's instructions for proper implementing;
3. Let the re-paired area with plaster to dry completely before re-painting the fence concrete;
4. The paint shall be of Baunit manufacturer quality or higher; the color of the paint to be the same as the existing one;
5. Before concrete re-painting starting, the plaster repair will be checked and approved by the FAC staff;
6. When painting, keep to instructions manual of the manufacturer; no spays to be used for painting;
7. Keep the metal part of the fence from painting;
8. When working inside the Embassy, the workers shall be minimum (4) and maximum (5) because of escorting;
9. Plaster and paint names shall be cited in the quotation for their approval by the customer;
10. Coordination with the Facilities engineer is required;
11. All used ladders by the contractor's workers shall be taken down and away every day before leaving the Embassy;
12. When the worked is finished, all wasted materials shall be taken away by the Contractor.

Roumen Pavlov

Facility Engineer

June 3rd, 2014