

# US Embassy LGF North-East Walkway repair

## Scope of Work

---

The existing LGF North-East Walkway, with total length about 212 meter and wide 1 meter, shall be repaired with a ready-mix concrete (about 2012 square meter), keeping to the following:

1. There are curbs on the both side of the walkway, and all those on its external rim shall be kept as far as they firm enough and not damaged; they will be used for final level; curb elements against the fence wall shall be dismantle together with all tiles of the existing walkway;
2. All tiles and construction materials rubbish shall be taken out from Embassy to approved by Sofia Municipality locations.
3. The finish level of the walkway shall be not higher than existing one; the path shall be inclined to the external rim not more than 2%
4. Where the slide lands happened, the soil shall be added and all that well stamped.
5. The depth of the new walkway shall be 20cm; half of it shall be concrete and the rest of it - rubbles.
6. To be provided enough space for strike-out board moving.
7. The thickness of the concrete shall be 10cm;
8. Air-entrapping additive to be provided in the concrete;
9. The concrete shall be of grade C25;
10. Reinforcement to be provided for the concrete with the min thickness of the steel 8 mm and sizes 15cm x 15cm;
11. The concrete shall be ready-mix only from Boiana concrete center;
12. Plastic sheets shall be provided for covering of the poured concrete and during its curing .
13. All work to be coordinated with Facility Engineer first;
14. See also the more detailed SOW in Bulgarian language.

Roumen Pavlov

Project manager

May, 2014