

STATEMENT OF WORK: NEC REC. Children Area-Earthworks

-The Earthworks at Children area consists of:

*Remove existing gravels; surface: 700 M²; thickness=10 CM

*Remove all existing debris and fabrics, surface: 700 M²

*Remove existing flowers along the metallic fence; surface: 65 M²

*To level ground to get a horizontal flat surface for carpets installation.

*At the end of the work, take out all debris, excess materials and left over things.

*Duration of the work is three weeks