

Questions and Answers
RFQ No. SCA52515Q0023
U.S. Embassy Chancery Resurface Patio Paver

1. Q: Contractors need information on the existing waterproof membrane under the existing sand bed?

A: The existing waterproof membrane is a MM6125 Hydrotech Monolithic Membrane.

2. Q: What type of waterproofing membrane do you require to be installed?

Given the durability of the Hydrotech membrane, no new waterproofing membrane is to be installed.

3. Q: Would you have a concrete mix for the new stamped concrete? What strength are you looking for (20mpa,30mpa, etc.)?

A: The concrete force is 35MPA with air.

4. Q: The "expansion joint" noted on your drawing is not a manufactured expansion joint, but a 25mm joint to be installed? Please clarify.

A: It is a 25mm joint along the existing wall and not a manufactured expansion joint.

5. Q: Is the successful contractor required to supply and install temporary fencing around the proposed plaza deck during the construction of the new stamped concrete pad?

A: Yes.

6. Q: Is the successful contractor required to supply and install temporary hoarding over windows and doors within the proposed plaza deck?

A: Yes.

7. Q: Please clarify the complete scope of work with the existing ground lighting fixtures – ie. after removing the light fixture, are there conduits to be removed, capped, etc.?

A: Conduits to be removed and capped.

Cleared by: Douglas S. Dobson, Contracting Officer