

United States Embassy Bogota
SOCCER FIELD & PLAYGROUND AREA REPAIR
Solicitation # SCO20016Q0014

Question #1- Regarding the item 1.3 - Dismount existing playground system. Please provide the plans of the playground which needs to be uninstalled.

Existing playground was seen during the site visit. It is currently a bolted wood system anchored with concrete bases approximately 0.8 mts deep.

Question #2 – Regarding the item 1.7 - Block and relocated ten existing trees. Please provide the size and type of tree.

7 small trees (2.00 meters eugenias) will be relocated.

3 Medium size (5.00 – 6.00 meter acacias) will be relocated.

Question #3- Regarding the item 3.3 - Benche & Planter (5.15 ID x 0.8 h x 0.10 thk), finished black granite # 1. Please provide detailed description about what is required.

This bench is cast reinforced concrete structure (see picture) that has a washed gravel finish according to the specifications in item 3.3.



Question #4- Regarding the item 4.1 - PVC Piping system for drainage. The unit measure is global, more information about quantities required.

A French drain system in the Green areas and surrounding the planter must be installed. The pipe will drain to an existing storm drain box. 60 linear mts +/- 5% of 4" perforated drain pipe will be used.

Question #5- Regarding the item 5.1 - Electrical and communication installations (lighting). The unit measure is global, more information about quantities required.

Approximately 80 linear mts will be needed to install two new exterior outlets. Minimum 1" PVC pipe for each circuit (approx. 40 mts each one). Each circuit will be at least for 20 Amps – 120V.

The electrical installation must follow all applicable codes.

Question #6 - Ítem 6.2 - Installation of new playground equipment. Please provide detailed information about the equipment to be installed in order to estimate performance and required personnel.

See attached details drawings.

Question # 7- Regarding the item 7.1 - Flower plant. Please provide the type of flowers required.

A variety of native exterior colorful plants similar to the existing gardens in the Embassy compound are expected. Approximately 20 sq.mts or garden area will be covered with these new plants.

Question #8- Regarding the item 7.3 – Trees. Please provide type, diameter and height.

A magnolia minimum 5.00 meters in height shall be installed in the new planter.