



**STATEMENT OF WORK
(SOW)
Installation of 24 Fiber Pairs**

1. INTRODUCTION

The U.S. Embassy needs to install 24 fiber pairs/48 strands from its Demarcation Room To The Main Distribution Frame (MDF) Room.

2. Fiber Installation

The work consists of, but is not limited to, the following: Providing and installing 24 pairs/48 strands of OM3 Multimode MM50 Microns exterior Fiber Optic. Provide and install the fiber distribution panels (FDP) and the termination of the fiber pairs, 48 strands – for a total of 96 terminations, at each end.

Cost

The price offered shall include all labor, materials, overhead (including cost of Workers' Compensation and Liability Insurance, which shall not be a direct reimbursement) and profit. All prices are in local currency and the US Government will make payment in local currency.

3. EXECUTION

Installation - the contractor shall ensure that personnel will observe safety measures in accordance with local regulations and norms. Contract must exercise extreme caution to avoid any structural or property damage. All damage(s) must be reported immediately and the contractor will be responsible for the cost related to the repair of the reported damage(s).

Debris Removal - The Contractor is responsible for the removal of all debris that is a direct result of this project. Contractor is authorized to use available trash bins to dispose of the collected debris.

Other - Contractor personnel shall not wander outside of the work area at any time, and they will be escorted at all times. The contractor will be responsible to remove prior approval of the Contracting Officer Representative (COR) all furniture that may be disrupting their work and put it back in place later on. They are responsible to cover and protect all equipment to avoid any damages.

END OF STATEMENT OF WORK