

**STATEMENT OF WORK  
(SOW)  
Installation of 156 Fiber Strands**

**1. INTRODUCTION**

The U.S. Embassy needs to install 156 fiber optic strands, 12 OM3 MM50 Microns multimode fiber optic cables, consisting of 13 strands each, from the telecommunications closets to its Main Distribution Frame located in the Ground floor.

**2. Fiber Installation**

The work consists of, but is not limited to, the following: Providing and installing 12 OM3 MM50 Microns multimode cables, termination of the fiber strands at each location, telecommunication closets and MDF, testing and certification of the installed fiber. The cables will be installed in the telecommunications closets located in, Ground floor North, 1<sup>st</sup> floor South and North, 2<sup>nd</sup> floor North and South, 3<sup>rd</sup> floor South and 4<sup>th</sup> floor South.

**Cost**

The price offered shall include all labor, materials, overhead (including cost of Workers' Compensation and Liability Insurance, which shall not be a direct reimbursement) and profit. All prices are in local currency and the US Government will make payment in local currency.

**3. EXECUTION**

**Installation** - the contractor shall ensure that personnel will observe safety measures in accordance with local regulations and norms. Contractor must exercise extreme caution to avoid any structural or property damage. All damage(s) must be reported immediately and the contractor will be responsible for the cost related to the repair of the reported damage(s).

**Debris Removal** - The Contractor is responsible for the removal of all debris that is a direct result of this project. Contractor is authorized to use available trash bins to dispose of the collected debris.

**Other** - Contractor personnel shall not wander outside of the work area at any time, and they will be escorted at all times. The contractor will be responsible to remove prior approval of the Contracting Officer Representative (COR) all furniture that may be disrupting their work and put it back in place later on. They are responsible to cover and protect all equipment to avoid any damages.

**END OF STATEMENT OF WORK**