

Solicitation# S-IZ250-16-Q-0106

New FAC Workshop and Storage Cages

Below are questions from contractors before and during the site visit and all questions answered by the Contracting Officer Representative.

Q1: What is the measurement of the existing building?

Answer: 282.89sqm

Q2: Provide layout or drawing for existing?

Answer: Negative. Per the scope of work the contractor shall submit drawings to COR within 5 days from the date of the NTP. Please, check F.05, F.09, B.04 and point b in page 7.

Q3: What is the height of the existing building?

Answer: No existing building – land only.

Q4: What is the thickness of the new concrete slab?

Answer: Slab thickness is 40cm (reinforcement concrete) with two layers of 12mm rebar.

Q5: Where we have to use the concrete blocks?

Answer: the concrete blocks will be used to build the two bathrooms (male and female). Hollow concrete block or thermostone block are approved to use.

Q6: What we can use for the office wall?

Answer: Office walls can be sandwich panel's 5cm thickness materials. The cover for the office will be the same materials and then contractor is required to install a drop ceiling for all office space.

Q7: How many stairways are required?

Answer: Two stairways are required. Location will be determined during the construction work.

Q8: Can we use thermoston block to block the space between the posts of the metal structural?

Answer: Yes, as listed on scope of work.