

## **Canopy Replacement Project**

**A/ STATEMENT OF WORK (SOW)** Project includes main work as below:

- Contractor shall provide and replace new canvas for:
  - 1/ The motorbike parking area, that includes two tents with the measurement:  
  
11.4 x 30 meter and 5.4 x 30 meter.
  - 2/ The parking tent with the measurement: 9 x 11 meter.
  - 3/ A moveable awning at IV waiting area with the measurement: 2 x 2.5 meter
  - 4/ Moveable awning along NIV waiting area with the measurement:  
  
Two of awning: 6.6 x 3.3 meter  
Seven of awnings: 7 x 6.9 meter.
  - 5/ This project includes repainting all metal parts, replacing two plastic rollers and a gear.

The canvas, rope, rollers and gear shall be the same quality as the existing ones.

**All dimensions mentioned above are just estimated; contractors shall make accurate measurement when they make site survey before submitting the quotation.**

**B/ SPECIAL NOTES:** Special notes should be made of the following:

- (a) All materials, equipment are to be used or installed for this project, shop drawings, working schedule shall be approved in advance by Contracting Officer of U.S. Consulate General (C.O), in accordance with recommendations of the manufacture.
- (b) Debris and other waste materials must not be allowed to accumulate on the site. Contractor will transport materials off U.S. government property and legally dispose of them on daily basis. Contractor must not burn any demolished materials on site.
- (c) Ensure that construction workers do not stray into warehouse and other restricted areas on the compound.
- (d) Contractor agrees to comply with U.S. Government security procedures on site at all times.
- (e) Contractor will comply with safety rules.
- (f) Contractor will not damage, break or breach the perimeter walls or adjacent facilities of COB in places other than that specified under the construction work.
- (g) Contractor will provide liability insurance for workers on site.

- (h) Contractor must outline his methodology (in his proposal) for the construction of the structure.
- (i) Toilet and parking facilities for workers during the construction time shall remain the responsibility of the contractor.
- (j) Ensure that planters and trees around the structure to be constructed are protected from damage and destruction.
- (k) It shall be the Contractor's responsibility to provide a completely safe and workable system in accordance with the requirements of this specification, and the accompanying drawings and schedules all to the entire satisfaction of the Contracting Officer.
- (l) The Contractor shall examine all accompanying drawings and specifications to make sure that all requirements are thoroughly understood. In case where, in his opinion, there are omissions and /or errors in any of these documents, he shall inform the Contracting Officer immediately.
- (m) All materials, equipment and finished works shall be kept in good condition. The complete work shall be the Contractors property until handed over to the U.S Government.

END OF SCOPE OF WORK