

**SCOPE OF WORK**  
**Tensile Structure at Swing Area**  
**Solicitation#SIN65014Q0099 dated August 4, 2014**

Fabricate and install tensile fabric shed/sail with necessary MS structure with complete painting, including all Ferrari fabric 702-S, fabric pocket with cables/edges cable with clamps, corner plates, steel cables, fork connectors, cylindrical connector, compression strut, cable hangers, turn buckles, base plates and all accessories complete.

- a. Approx. area of shed/sail is 80 sq.mts.
- b. Total 15 working days shall be given to complete the job.
- c. Before fabrication contractor shall get the drawings approved.
  
- b. Providing tensioned fabric shed: cable / frame supported tensioned membrane - covered fabric structure incorporating a fabric with low elongation characteristic under tension and capable of an anticlastic configuration.
- c. The contractor shall variety and incorporate requirement of additional supports.

The contractor shall provide the details, drawings, fabrication and installation of work specified in the items before execution of work at site.

**NOTE:-**

1. Fabric applied with flat or mono-axially curved configuration is not acceptable.
2. The detailed drawings will be provided in accordance with the reference design shown in sketches (copy attached). New design provided by the contractor shall be compatible as per the site requirements.

**General Note:**

1. All material used for above job shall be approved before using.
2. The contractor shall see the actual work involved during the walk through.
3. The contractor shall provide all the material as per scope of work.

4. The contractor is responsible for any damage to the property during the work and it shall be restored by the contractor at his own cost, matching to existing.
5. The contractor shall take exact measurements of the cabinet before fabrication.
6. If any service is interrupted as a result of this work, it should be immediately restored and any damage caused shall be rectified by the contractor at his own cost.
7. Any material, which is unsatisfactory, should be removed from the site immediately.
8. All material and supporting material for this job or any type of tools etc. will be arranged by the contractor to complete the job unless mentioned in the scope of work.
9. Working hours shall be 0830 to 1730.
10. The contractor shall not take orders and/or instructions from any persons except the contracting officer or his assigned representative.
11. Contractor will work with all the safety and precautions to prevent injury to employees and workers and he will be responsible for any untoward incident on the site.



**Designs For Reference**

