AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT	1. CONTRACT ID CODE	PAGE 1 OF 4

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. *(If applicable)*
A002	See Block 16.C.		

6. ISSUED BY CODE	7. ADMINISTERED BY *(If other than Item 6)* CODE
U.S. American Embassy Al Kindi Street International Zone Baghdad, Iraq	

8. NAME AND ADDRESS OF CONTRACTOR *(NO., street,city,county,State,and ZIP Code)*		9a. AMENDMENT OF SOLICITATION NO.
	X	S-IZ100-13-Q-0011-A001
		9b. DATED *(SEE ITEM 11)* March 24, 2013
		10a. MODIFICATION OF CONTRACT/ORDER NO.
		10b. DATED *(SEE ITEM 13)*

11. **THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

[✓] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [ ] is extended, [✓] is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning _1_ copies of the amendment;(b) By acknowledging receipt of this amendment on each copy of the offer submitted; or(c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. **FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER.** If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. **ACCOUNTING AND APPROPRIATION DATA** *(If required)*

13. **THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation date, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER *(Specify type of modification and authority)*

E. **IMPORTANT:** Contractor [ ] is not, [X] is required to sign this document and return _1_ copies to the issuing office.

14. **DESCRIPTION OF AMENDMENT/MODIFICATION** *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The solicitation is hereby amended to read as follows:
See continuation page.

(continuation on next page)
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME OF CONTRACTING OFFICER Stan Parmentier	
15B. NAME OF CONTRACTOR/OFFEROR BY _____ *(Signature of person authorized to sign)*	15C.DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ *(Signature of Contracting Officer)*	16C.DATE SIGNED 03-26-2013.

1) SECTION 1 – THE SCHEDULE, 1.3 U.S. Government Furnished Property (GFP) is amended to read:

ITEM LIST - A	KEY FOR LOCATION	Quantity	Type of Connection	GFE Material
WARDROBE	F2	568	Seismic connections	Tip Resistant Safety Bracket (FSB 100)
STORAGE CABINET (915W x 815D x 1626H)	ST1	2	Seismic connections	Tip Resistant Safety Bracket (FSB 100)
TELEVISION – 26"	T3	568	Wall mounting, Patch cord connection. Plug in the Power Cord.	Wall mounting Bracket; 2m long Coaxial cable with connectors on both ends. Power cord is standard attachment.
TELEVISION – 52"	T7	16	Wall mounting, Patch Cord connection. Plug in the Power Cord.	Wall mounting Bracket; 2m long Coaxial cable with connectors on both ends. Power cord is standard attachment.
WASHER	W	40	Water inlet, Drain connection. Plug in the Power Cord.	Inlet flexible pipe with connector and outlet flexible pipe are with the washer. Power cord is standard attachment.
DRYER	D	40	Air exhausts connection. Plug in the Power Cord.	None.
DVD PLAYER	Kept on Desk –D1	568	Patch Cord Connection. Plug in the Power Cord.	Patch Cord. Power cord is standard attachment.
REFRIGERATOR	E1 AND E6	584	Plug in the Power Cord.	Power cord is standard attachment in the refrigerator.
MICROWAVE OVEN	E2	32	Plug in the Power Cord.	Power cord is standard attachment in the microwave oven.
FLOOR LAMP & END TABLE LAMP	L1 AND L2	1,168	Install bulb. Plug in the Power Cord.	Power cord is available as standard attachment in the lamp. Bulb (incandescent 60Watts, Daylight, E26 medium base bulb.). Option: Contractor to price for supply of bulb.
Door sliding lock.	All shared bathroom doors.	548	Install sliding lock.	None.

2) SECTION 1 – THE SCHEDULE, 2. SCOPE OF WORK is amended to read as follows:

2.2 Seismic Connections: Install seismic connections for Wardrobe and Storage cabinet, as indicated in attached sketch-1; in accordance with the seismic restraint manufacturer's instructions. Depending on the wall material where the restraint is installed, contractor will need to provide appropriate anchors. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.3 Wall mounting of Television set (26" / 56"): Install the wall mounting bracket, as indicated in wall mounting bracket manufacturer's instructions. Install televisions and brackets in a rigid manner, straight and plumb. Contractor to provide appropriate anchor to fix the bracket on CMU (Concrete Block Masonry Unit) wall. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.4 Installation of coaxial cable for Television set (26" / 56"): Connect the coaxial cable provided to the wall signal outlet and to the TV signal inlet port per manufacturer's instructions. Plug in the power cord to the wall power socket provided. Test run the television set and report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.5 Washer water inlet connection: Connect all washing machines to the existing plumbing connection utilizing the manufacturer's recommended washers and seals. The contractor shall test the connection for leaks and shall repair or replace any damaged equipment or hose connections. Plug in the power cord to the wall power socket provided. Test run for the washer and report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.6 Washer drain outlet connection: Connect all washing machines to the existing plumbing connection utilizing the manufacturer's recommended washers and seals. The contractor shall test the connection for leaks and shall repair or replace any damaged equipment or hose connections. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.7 Dryer air vent outlet connection: Procure flexible metal (foil type) duct connection and clamps, suitable for the hot air vent connection from the dryer vent collar to the air vent duct that is 4" in diameter. Procure power plug and power cable recommended by the manufacturer. Submit a sample with product data (Flexible duct, clamps, power plug and power cable) for approval of the COR prior to procurement. Connect and clamp the flexible duct to the 4" wall air vent duct provided and to the 4" air vent outlet collar provided in the machine. Plug in the power cord to the wall power socket provided. Test run for the dryer and report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.8 DVD Player Connection: Connect the coaxial cable provided with the player to the signal outlet port of the DVD player and to the TV signal inlet port per the manufacturer's instructions. Plug in the power cord to the power socket provided in the wall. Test run the television set and the DVD player; report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.9 Refrigerator Connection: Plug in the power cord to the power socket provided in the wall. Test run the refrigerator; report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.10 Microwave oven: Plug in the power cord to the power socket provided in the wall. Test run the Microwave; report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation.

2.11 Floor lamp and End Table Lamp: Install the bulb provided, into the lamp holder. Plug in the power cord to the power socket provided in the wall. Test the functionality of the lamp; report the result. Perform a mockup installation and obtain COR's approval, prior to proceeding with installation. Option: Contractor to price for supply of incandescent 60Watts, Daylight, E26 medium base bulb.

2.12 Procure and install sliding lock: Procure sliding lock similar to the one shown in Attachment 2A. Length approximately 4" (100mm), satin finish, stainless steel or closely matching the finish of installed door hardware. Install the sliding lock as shown in the Attachment 2A, on the sleeping room side of the toilet doors. Drill a hole in the door jamb, as shown in Attachment 2A (The catch plate cannot be installed as the door face is not flush with the jamb.) for the bolt to slide in and secure the door. The hole edges to be smooth finished and paint touched up. The paint used for touch up has to match the existing paint type and color.
Work requires submission of samples, method of installation and making a mockup installation for approval. Proceed with work upon approval of samples, method of installation and mockup by the COR.