Requisition Number: PR5592265

Requisition Title: R07 BOREHOLE STORAGE WATER TANK OVERHAUL SERVICE

Purchase Request: PR5592265
Request Type: Requisition
Requesting Office: AMERICAN EMBASSY NAIROBI
Issued on Fri, 05 Aug, 2016
Created on Fri, 05 Aug, 2016 by Peter C Ruheni

Vendor:

NOVENDOR
,
UNITED STATES

Ship To:

Department of State
U.N. AVENUE GIGIRI; PO BOX 606,00621
ATTN: FM-RESIDENTIAL - 1901.0
NAIROBI
KENYA

Deliver To:
FM/NEC

Bill To:

Department of State
UNIT 64100
ATTN: US EMBASSY FMC
APO, AE 09831-4100
UNITED STATES

Funding:

Type	Amount(Local Currency)	Amount(USD)	Details
Commodity Accounting Line	$0.00 USD	$0.00 USD	----------

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
1	**Undertake pre-construction survey work, ...**		each	1	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD

Undertake pre-construction survey work, mobilize site with adherence to safety, occupant's convenience and quality of work, and make good the site upon completion. Note that cleaning and paint work is subject to confined space risk management as per US government policy and therefore proper precaution and documentation is required.

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
2	**Supply of 6 pcs 4"class B GI Galvanized pipe ...**		meter	18	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD

Supply of 6 pcs 4"class B GI Galvanized pipe including elbows, unions, tee and associated fittings and replace the existing. Allow for proper anchoring of the pipes on the walls and other applicable structures.

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
3	**Supply and install 4" Butterfly valve ...**		each	1	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD

Supply and install 4" Butterfly valve fabricated and fitted with chain based winch for aided opening and closing

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
4	**Carry out surface preparation, sanding and ...**		square meter	200	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD
	Carry out surface preparation, sanding and application of external paint on the outside surface of the tank including support and pipe structures. Primer and two coats of silver/aluminum gloss paint shall be applied						

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
5	**Drain the overhead tank, undertake thorough ...**		each	1	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD
	Drain the overhead tank, undertake thorough cleaning and allow drying for paint work to be done on the internal surfaces of the tank.						

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
6	**Undertake Surface preparation and sanding ...**		square meter	180	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD
	Undertake Surface preparation and sanding plus application of BASF Master Protect 180(or equivalent high quality water proofing product) on the internal surfaces of the tank. Provide product catalogue and MSDS						

Item	Description	Part Number	Unit	Qty	Need By	Unit Price	Extended Amount
7	**Undertake repair work on associated feature ...**		each	1	Sat, 20 Aug, 2016	$0.00 USD	$0.00 USD
	Undertake repair work on associated feature of the tanks including: lid, lid hinges and fasteners, joint bolt work, ladder, bracings						

						Total	$0.00 USD

Status: Submitted

Approvals

Required	Status	Reason	Approver	Approved By	Date
Required	Approved		Saini Vikas	Saini Vikas	Tue, 09 Aug, 2016
Not Required	Ready	Approver 6: Watcher - Optional Approver	Nairobi Watcher Group		
Required	Approved	Approver 1: Organizational Approver 1	Nairobi FM Approvers	Mark Grantham	Thu, 11 Aug, 2016
Required	Ready	Approver 3: Procurement Team	Nairobi Procurement Team		
Required	Pending	Approver 4: B&F	Nairobi Accounting		
Required	Pending	Approver 5: FMO	Nairobi FMO Group		
Required	Pending	Approver 7: Final Approver	Nairobi Contracting Officers		

Requisition Comments

- Peter C Ruheni, 08/05/2016: