

QUESTIONS & ANSWERS

SOLICITATION # SKU20016Q0025 – PR5561989 - Renovate/Refurbish Toilets in Embassy Compound.

Question	Answer
1. Elevation for ALL Bathrooms	Photos are provided. Elevation to match/be similar to existing. Please refer to Amendment# 01
2. Dimensions L x B x H	LxWxH Warehouse Female Bathroom 153cmx297cmx274cm Front Gate Bathroom 178cmx165cmx281cm SDH Gate Bathroom 222cmx200cmx246cm Back Gate Bathroom 188cmx180cmx257cm
3. Is floor base resurfacing & leveling for water seepage to drain outlet, required	Yes, for bathrooms that get new floor tile, correct grout/mortar bed leveling bed adjustments are required to slope to drain.
4. Description of Door Work	Scope of work requires preparing (sanding, scraping/removing paint), and repainting (semi-glos soil based) primer + finish coat of both the door (all sides) and door frame. The door threshold is to be removed and replaced.
5. Description of inside Ceiling Work	Listed in the SOW. In bathrooms that get new ceiling tiles only: the contractor will remove and replace the ceiling tiles with new ceiling tiles per the specifications. All existing ceiling grid in all locations should be sanded, prepped and re-painted. Front gate bathroom – completely new ceiling tile system and tiles per the SOW.
6. In light of the above respective questions and convenience	Refer to Amendment# 01. Bid closing date extended to September 15, 2016.
7. See addition:	Women’s bathroom in the warehouse is to receive new floor tile. (Remove existing, including grout, install new floor tiles and base).