

## SOLICITATION RFQ# S-KU20015Q0010 – RTO LAYDOWN PAD PROJECT

### QUESTIONS & ANSWERS

Question	Answer
1. What is the linear measurement in meters for fencing?	- Approximately 110m +/-
2. What is the linear measurement in meters for Conduit trenching & the size of electrical cable?	- Approximate length is 75m – 80m - Cable should be #10A WG (6mm <sup>2</sup> ).
3. Is it a must that all the labours assigned for this project should be under one sponsor (Residence Permit)	- Yes. All Personnel working under this project must be under the main contractor. However, tier 1 subcontractor services are allowed for crane & heavy equipment services only.
4. What is the length of the barbed wire outriggers?	- From fence top to outer point of the outrigger should be 20-22", with the 3 strands of barbwire evenly space along its length. - Fence posts must be set in a concrete foundation, that is 300mm x 300mm x 500mm deep. - Top of Fence post minimum 3m from ground. - Bottom to be fully set into concrete base - Post to be 60.3mm OD (outer diameter) & Schedule 40 thickness. - Corner posts 73mm OD (outer diameter).

