

Building name: American Embassy PAO office
 Address: Samnera Velsa street 1, Riga

No	Works title	Measurement	Quantity	Unit costs (euro)	Sum (euro)
1	Door demolition	pcs	1		
2	Gypsum board partition cutting	m ²	11		
3	Removing kitchen cabinets, cutting stone counter	m	2.1		
4	Cover floor with cartoon and furniture with plastic to protect from dust	room m ²	123		
5	Dry wall building with sound isolation	m ²	20		
6	Ceiling tile repairing at Office 2 after dry wall construction	m ²	3		
7	Built in wall Hallovolt LF EMC conduit d20mm	m	6		
8	Built in wall Hallovolt junction box	pcs	2		
9	Built in wall power outlets, add electricity	pcs	8		
10	Aluminium door D-1 installation	pcs	1		
11	Aluminium door D-2 installation	pcs	1		
12	Aluminium window WD-1 installation	pcs	1		
13	Wall painting with 2 coats with latex paint at Office 1 and Meeting room	m ²	210		
14	Wall filling, priming and painting with 2 coats with latex paint at Office 2	m ²	55		
15	Carpet tiles Forbo "Flotex Integrity" installation at Meeting room	m ²	17		
16	Baseboard installing at Office 2 and Meeting room	m	36		
17	Threshold installations between rooms	pcs	4		
18	Office complete cleaning	room m ²	123		
	TOTAL				

Note:

The contractor should have a full tender offer price, including ancillary works and materials, which are not shown in the list and volume of the project, but are necessary for the design of the office renovation and commissioning.

architect Guntis Muižzemnieks