

U.S. Embassy
Proposed BMS Points List



NOTE: Respective MEPF equipment schedule and schematics shall govern in case of conflict with the quantities stated in this points lists.

Items	Equipment/Items	DO	DI	AO	AI	High Level Interface	Remarks
MECHANICAL							
1 CHILLED WATER PLANT SYSTEM							
1.a WATER COOLED CHILLER							
	- Chiller start/stop	X				X	The Chiller itself with Chiller Plant Manager shall be of HIGH LEVEL INTERFACE. Chiller Plant Contractor shall ensure this provision. It should be capable of both LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- Chiller On/Off Status		X			X	
	- Chilled Water Supply Flow Sensor		X			X	
	- Chilled Water Supply Pressure				X	X	
	- Chilled Water Return Pressure				X	X	
	- Chilled Water Supply Temperature				X	X	
	- Chilled Water Return Temperature				X	X	
	- Chilled Water Return Flow Meter					X	
	- Condenser Water Return Flow Sensor		X			X	
	- Condenser Water Supply Pressure				X	X	
	- Condenser Water Return Pressure				X	X	
	- Condenser Water Supply Temperature				X	X	
	- Condenser Water Return Temperature				X	X	
	- Kw-Hr Monitoring				X	X	
1.b CHILLED WATER MAINS							
	- Chilled Water Return Temperature	1			X		
1.c PRIMARY CHILLED WATER PUMP w/ VFD (NEW)							
	- Start/Stop	X				X	PUMP with VFD shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- Pump Speed Control			X		X	
	- Pump Speed Monitoring				X	X	
	- Flow Meter				X	X	
	- Kw-Hr Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
1.d PRIMARY CHILLED WATER PUMP (OLD)							
	- Start/Stop	X				X	PUMP shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- Flow Meter				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
1.e SECONDARY CHILLED WATER PUMP w/ VFD (NEW)							
	- Start/Stop	X				X	PUMP with VFD shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- Pump Speed Control			X		X	
	- Pump Speed Monitoring				X	X	
	- Flow Meter				X	X	
	- Kw-Hr Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
1.f CONDENSER WATER PUMP w/ VFD (NEW)							
	- Start/Stop	X				X	PUMP with VFD shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- Pump Speed Control			X		X	
	- Pump Speed Monitoring				X	X	
	- Flow Meter				X	X	
	- Kw-Hr Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
1.g CONDENSER WATER PUMP (OLD)							
	- Start/Stop	X				X	PUMP shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- Flow Meter				X	X	
	- Pressure Monitoring				X	X	
	- Pressure Monitoring				X	X	
1.h COOLING TOWER							
	- Start/Stop	X				X	Cooling Tower shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
	- On/Off Control Valve	X				X	
	- Return Temperature Monitoring				X	X	
	- Flow Sensor		X			X	
	- Pressure Monitoring				X	X	
	- Sump Temperature Monitoring				X	X	
	- Kw-Hr Monitoring				X	X	
	- Kw-Hr Monitoring				X	X	
1.i SAND FILTER UNIT							
	- Start/Stop	X				X	Sand Filter Unit shall be of HIGH LEVEL INTERFACE. Contractor shall ensure this provision. It SHOULD BE CAPABLE OF BOTH LONWORKS AND BACNET PROTOCOL. Signal type will be guide in virtual configuration.
	- On/off Status		X			X	
	- Trip Alarm		X			X	
1.j DIFFERENTIAL PRESSURE TRANSMITTER							
		2			X		

1 BMS POINTS LIST
EC2-03 NTS

UNITED STATES EMBASSY
MANILA, PHILIPPINES



FACILITIES MANAGEMENT

WARNING:
This document is the property of the U.S. Government. Further reproduction and/or distribution is prohibited without the express written permission of:
FOREIGN BUILDING OPERATIONS
U.S. Department of State, Washington, DC, 20522-0620
Information on this document is not to be altered except with the written approval of the individual whose seal appears hereon.

**SENSITIVE
BUT
UNCLASSIFIED**

Engineer
MEINHARDT
25th Floor Chatham House 116 Valero cor.
V.A. Rufino St. Salcedo Village, Makati City
Tels. (632) 887-1391 E-mail mpi@meinhardt.com.ph
Fax (632) 887-1172

**RAYMOND C. MEDINA, ASEAN-APEC
PROFESSIONAL ELECTRONICS ENGINEER**

PRC Reg. No: 72 PTR No: 3178284

Date: JANUARY 04, 2012 Place: MAKATI CITY

APPROVED BY :

DISCIPLINE	INITIAL	SIGNATURE	DATE
SFM	PLS		
DFM	RLW		
CIVIL/STRL			
ELECT'L			
MECH'L			

RevNo	Revision note	Date	Sign.

Project Title

**US EMBASSY
MAIN CHILLER
PLANT ADDITION**

Location
ROXAS BOULEVARD, PHILIPPINES

Release For Construction:
FMM FMS

SHEET CONTENT
**ELECTRONICS SERVICES
BMS POINTS LIST**

Phase
 CONCEPT 30% 60% 90% 100% FINAL

Date 29OCT12	CADD File Name -
Designed PGL	Drawn By MMN
Checked RCM	Drawing Number EC2-03
Project Number MP1044	Sheet Number Sheet 6 of 7

FOR TENDER

Contract No.
CONTRACT_NO