

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE
PAGE OF PAGES
1 5

2. AMENDMENT/MODIFICATION NO. A-001	3. EFFECTIVE DATE 8/28/2014	4. REQUISITION/PURCHASE REQ. NO. PR3607200	5. PROJECT NO. (If applicable)
6. ISSUED BY Contracting & Procurement General Services Office, American Embassy Manila Seafront Compound, Roxas Boulevard, Pasay City		7. ADMINISTERED BY (If other than Item 6)	

8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State, and ZIP Code)	(√)	9A. AMENDMENT OF SOLICITATION NO. SRP380-14-Q-0102
	X	9B. DATED (SEE ITEM 11) 08/28/2014
		10A. MODIFICATION OF CONTRACT/ORDER NO.
		10B. DATED (SEE ITEM 13)
FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers --Is extended, is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; of (c) By separate letter of telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.


(√)	A.	THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B.	THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)
	C.	THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D.	OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return ___ copy to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

SRP380-14-Q-0102 is being amended as follows:

1. Under scope of Work:
 - a. Item 7b. delete statement and replace with Cut thru wall and install new Solid Core Door including Door Frame and **Rim Panic Device**, including accessories.
 - b. Item 7k. delete statement and replace with Remove existing Carpet Floor Tiles and replace with new 600mm x 600mm **Carpet Floor Tiles, Install new Vinyl Base Board**
 - c. Include new item 7l. **Construct new 850mm high counter with Plastic Laminate Finish.**

15A. NAME AND TITLE OF SIGNER (Type of print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or Print) ALEXANDER K. HARDIN	
15B. CONTRACT/OFFEROR (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA  (Signature of Contracting Officer)	16C. DATE SIGNED 8/27/14

<u>CONTINUATION SHEET</u>	REFERENCE NO. OF DOCUMENT BEING CONTINUED SRP380-14-Q-0102	PAGE 2 of 2 Pages
NAME OF CONTRACTOR		

2. Under Section I, List of Attachments, include Demolition Plan as part of the Drawings.

3. All other terms and conditions remain unchanged and in full force and effect.

PROPOSED RENOVATION WORKS AT ICITAP OFFICE

SCOPE OF WORK

1. Prior to start of any work, the Contractor shall make arrangements to meet with the Contracting Officer's Representative (COR) at the Work Site for the purpose of Field Inspection. Actual measurements and conditions at the work site shall be verified by the Contractor.
2. The Contractor shall not begin the abovementioned project until proper authorization is received from the COR.
3. All existing spaces/areas therein shall be isolated from work operations, or distract the work of the personnel within the aforesaid area.
4. The Contractor shall fence-off the area of responsibility with yellow caution tape. Proper care shall be observed at all times to prevent damages, accident, or harm to personnel, structures, facilities, or surfaces.
5. All work operations shall prevent damages to materials, equipments, and other adjacent spaces.
6. Remove existing utilities that are said to be removed, and terminate in a manner conforming to the nationally recognized code covering the specific utility, and approved by the COR. If utility lines are encountered that are not shown or mentioned in the plan, contact the COR for further instructions.
7. Please refer to accompanying Layout Plan for the Scope of Works.
The work shall consist of but not limited to:
 - a. Remove existing door including door jamb; and block-off door opening using same materials as existing.
 - b. Cut thru wall and install new Solid Core Door including Door Frame and **Rim Panic Device**, including accessories. } A-001
 - c. Demolish existing recessed Entrance, and remove double-swing Entrance Door.
 - d. Rectify door opening and install new single-swing Entrance Door.
 - e. Install new partition up to ceiling height using metal studs and gypsum board, provide new entrance door as necessary; paint and surface finish to match existing.
 - f. Install new 1000mm H x 1500mm W fixed, clear window panel.
 - g. Perform Electrical Works as required (lighting and conduit layout, voice and data layout). Relocate all affected lighting fixtures.
 - h. Remove all existing acoustic ceiling boards and replace with new acoustic ceiling boards, use same materials as removed.
 - i. Relocate all affected air conditioning ceiling diffusers as required.
 - j. Perform Painting Works as required.
 - k. Remove existing Carpet Floor Tiles and replace with new 600mm x 600mm **Carpet Floor Tiles, Install new Vinyl Base Board**. } A-001
 - l. **Construct new 850mm high counter with Plastic Laminate Finish.**

8. Repair items which are damaged, or replace damaged items with new undamaged items as approved by the COR without additional cost to the Government.
9. All rubbish located within the limits of construction area will be considered job related and will require removal from the premises by the Contractor.
10. The Contractor shall assume full responsibilities and will be held liable for all damages inflicted on property and physical injury to workmen engaged in collection and disposal of construction debris generated by this contract.
11. Domestic rubbish containers on the premises **shall not** be utilized by the Contractor for storage or disposal means for construction rubbish.
12. Rectify all affected and/or damaged surfaces, and painted to match existing.
13. Smoking is strictly prohibited at the work site.
14. Debris shall be collected and removed from the job-site daily.
15. The Contractor guarantees to complete the work within **Thirty (30)** working days from the date of Notice to Proceed.