AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF PAGES
	1	1

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. *(If applicable)*
A001	9/21/2016	PR5560025	

6. ISSUED BY CODE
Contracting & Procurement
General Services Office, American Embassy Manila
Seafront Compound, Roxas Boulevard, Pasay City

7. ADMINISTERED BY *(If other than Item 6)* CODE

8. NAME AND ADDRESS OF CONTRACTOR *(No., street, county, State, and ZIP Code)*

FACILITY CODE

(√)	
	9A. AMENDMENT OF SOLICITATION NO. SRP380-16-Q-0177
x	9B. DATED *(SEE ITEM 11)* 09/9/2016
	10A. MODIFICATION OF CONTRACT/ORDER NO.
	10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☐ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ --Is extended, ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; of (c) By separate letter of telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

(√)		
	A.	THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B.	THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation date, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)
	C.	THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D.	OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not, ☒ is required to sign this document and return ____ copy to the issuing office.

14. DECRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

SRP380-16-Q-0177 is being amended to update the attached excel file.
To delete the following line items from the attached excel file for both Staff Apartment and Townhouse as follows:

Townhouse
1) Line item 59 Power Outlet 120VAC & 220VAC with wires and conduits
2) Line item 60 PVC False Colum (to cover the new riser 2 inches PVC Conduit/Pipe)
3) Line item 61 Restoration Cost for all affected and damages to its original conditions/ etc.
Staff Apartment
1) Line item 66 Power Outlet 120VAC & 220VAC with wires and conduits
2) Line item 67 PVC False Colum (to cover the new riser 2 inches PVC Conduit/Pipe)
3) Line item 68 Restoration Cost for all affected and damages to its original conditions/ etc.

All other terms and conditions remains the same.

15A. NAME AND TITLE OF SIGNER *(Type of print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or Print)* JOHN A. KLIMOWSKI	
15B. CONTRACT/OFFEROR *(Signature of person authorized to sign)*	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA *(Signature of Contracting Officer)*	16C. DATE SIGNED 9/21/16

List of Materials to be used for Telecommunication System Upgrade at Staff Apt. Building

Item no.	Specification	Quantity	unit	Unit Price	Cost
1	Main Patch Panel w/Wooden Cabinet enclosure/Varnish Finished - Wall mount	18	sets		
2	4 Gang/Quad faceplate - white color, Panduit Brand	80	pcs.		
3	CAT5e-RJ 45 Modular Jack - Blue, Panduit Brand	114	pcs.		
4	CAT5e-RJ 45 Modular Jack - Orange, Panduit Brand	114	pcs.		
5	CAT5e-RJ 45 Modular Jack - White, Panduit Brand	54	pcs.		
6	RG6 Modular Jack/F-Type - U.S. Brand	114	pcs.		
7	Surface Mounted /Plastic/Utility Box for 4 Gang Jack, Panduit Brand	80	pcs.		
8	CAT6 Cable-8 Wires, UTP, Blue Color, 1000 ft per box, U.S. Brand	12	box		
9	CAT6 Cable-8 Wires, Shielded Cable, Outdoor Type, 1000 ft per box, U.S. Brand	10	box		
10	CAT6 Cable-8 Wires, UTP, Orange Color, 1000 ft per box, U.S. Brand	12	box		
11	RG6 Coaxial Cable, 1000 ft per box. U.S. Brand	12	box		
12	RG11 Coaxial Cable/Outdoor Type, 1000 ft per box. U.S. Brand	5	box		
13	Patch Panel/CAT5e/CAT6/24 Ports - 19 inches rack-mount for Voice/LAN/CATV	5	sets		
14	Cable Guide - 19 inches Rack-mount	3	sets		
15	Main Distribution Box/NEMA 3R (12 x 12 x10) with hinged Cover. U.S. Brand	20	sets		
16	Telecommunication Cabinet -18U/19 inches Rack & Wall-mount cabinet	1	set		
17	Pull Box/NEMA 3R (16 x 16 x 12). U.S. Brand	2	sets		
18	Square Box, 4-11/16 x 4-11/16 x Depth Type, KO = 3/4 icnh with cover. U.S. Brand	54	pcs.		
19	LL Condulet-3/4 inch in dia.. U.S. Brand	90	pcs.		
21	12mm x 400 mm x 4mm thick Cable Tie, black color (100 pcs. per pack)	5	packs		
22	Silicon sealant	18	tubes		
23	3/4 inch in dia. PVC Pipe x 10 long, Sch. 40 - Neltex Brand	190	pcs.		
24	2 inches in dia. PVC Pipe x 10 long, Sch. 40. - Neltex Brand	45	pcs.		
25	3 inches in dia. PVC Pipe x 10 long, Sch. 40. - Neltex Brand	25	pcs.		
26	1 inch in dia. Plastic Molding with adhesive - U.S. Brand Brand	140	pcs.		
27	3/4 inch in dia. PVC Elbow -Neltex Brand	54	pcs.		
28	1 inch in dia.Plastic Molding Elbow - U.S. Brand Brand	54	pcs.		
30	2 inches in dia. PVC Elbow -Neltex Brand	30	pcs.		
31	3 inches in dia. PVC Elbow -Neltex Brand	10	pcs.		
32	3/4 inch in dia. PVC box connector - Neltex Brand	260	pcs.		
34	2 inches in dia. PVC box connector - Neltex Brand	55	pcs.		
35	3 inches in dia. PVC box connector - Neltex Brand	16	pcs.		
36	3/4 inch in dia. Locknut	520	pcs.		
38	2 inches in dia. Locknut	60	pcs.		

39	3 inches in dia. Locknut	20	pcs.		
40	3/4 inch in dia. Bushing	260	pcs.		
41	2 inches in dia. Bushing	55	pcs.		
42	3 inches in dia. Bushing	16	pcs.		
43	3/4 inch in dia. Clamp - Malleable Tyoe	380	pcs.		
44	Assorted unitrust clamp, bracket, hanger, and box/pipe supports	1	lot		
45	Anchor Bolt - 3/8 inch in dia. X 2 inches long. U.S Brand	100	pcs.		
46	Anchor Bolt - 1/4 inch in dia. X 1-1/4 inches long. U.S Brand	160	pcs.		
47	Wall anchor - 5/16 inch x 1 inch in dia. Long, 100 pcs. box	5	boxes		
48	Consumable Materials	1	lot		
49	½ inch (13mm) nylon cord (1000 meters/Roll)	2	rolls		
50	Conceret Cement, Portland Brand	100	bags		
51	Sand	180	bags		
52	Gravel	320	bags		
53	Stainless Plate Cover w/ lifting handle for Handhole, 17 inches x 17 inches x 1/4 inch Thickness, Grade 304	6	pcs.		
54	12mm Round Bar x 20 feet long	30	pcs.		
55	10 mm Round Bar x 20 feet long	14	pcs.		
56	GI Wire	7	kilos		
57	1/4 inch Flywood, 4 feet x 8 feet long	12	pcs.		
58	Wood Lumber, 2 x 2 x 10 feet long.	21	pcs.		
59	3 inches long Ordinary Nail	5	kilos		
60	1 inch long Ordinary Nail	3	kilos		
61	QDE Paint - White, Boysen Brand	24	gal.		
62	Paint Brush, 2 inch wide	24	pcs.		
63	Paint Brush, 1 inch wide	24	pcs.		
64	Assorted Tinting color	10	pint		
65	Electrical Caution Tape - 3 inch Wide x 1000 feet per roll - U.S. Brand	10	rolls		
~~**66**~~	~~Power Outlet 120VAC & 220VAC with wires and conuits~~	~~1~~	~~lot~~		
~~**67**~~	~~PVC False Column (to cover the new riser 2 inches PVC Conduit/Pipe)~~	~~1~~	~~lot~~		A001
~~**68**~~	~~Restoration Cost for of all affected and damages to its original conditions/etc.~~	~~1~~	~~lot~~		
				TOTAL COST PHP	**-**

List of Materials to be used for Seafront Telecommunication System Upgrade at Townhouse Units/Building

Item no.	Specification	Quantity	unit	Unit Price	Cost
1	Main Patch Panel w/enclosure - Wall mount w/ 6 phone jacks-RJ45 (blue) & 6 LAN jacks-RJ45 (orange) - Wall mount	24	sets		
2	4 Gang/Quad faceplate - white color, Panduit Brand	93	pcs.		
3	CAT5e-RJ 45 Modular Jack - Blue, Panduit Brand	130	pcs.		
4	CAT5e-RJ 45 Modular Jack - Orange, Panduit Brand	130	pcs.		
5	CAT5e-RJ 45 Modular Jack - White, Panduit Brand	165	pcs.		
6	RG6 Modular Jack/F- Type - U.S. Brand	130	pcs.		
7	Surface Mounted Box/Plastic//Utility Box 4 Gang Jack, Panduit Brand	93	pcs.		
8	CAT6 Cable-8 Wires, UTP, Blue Color, 1000 ft per box, U.S. Brand	14	box		
9	CAT6 Cable-8 Wires, Shielded Cable, Outdoor Type, 1000 ft per box, U.S. Brand	12	box		
10	CAT6 Cable-8 Wires, UTP, Orange Color, 1000 ft per box, U.S. Brand	14	box		
11	RG6 Coaxial Cable, 1000 ft per box. U.S. Brand	14	box		
12	RG11 Coaxial Cable/Outdoor Type, 1000 ft per box. U.S. Brand	6	box		
13	Telecommunication Cabinet -18U/19 inches Rack & Wall-mount cabinet	1	set		
14	Patch Panel/CAT5e/CAT6/24 Ports - 19 inches rack-mount for Voice/LAN/CATV	5	sets		
15	Cable Guide - 19 inches Rack-mount	2	sets		
16	Main Distribution Box/NEMA 3R (12 x 12 x10) with hinged Cover. U.S. Brand	24	sets		
17	Pull Box/NEMA 3R (16 x 16 x 12). U.S. Brand with Hinges Cover	8	sets		
18	Pull Box #1 /NEMA 3R (12 x 12 x 10). U.S. Brand with Hinges Cover	24	sets		
19	Pull Box #2 /NEMA 3R (8 x 8 x 6). U.S. Brand with Hinges Cover	24	sets		
15	Square Box, 4-11/16 x 4-11/16 x Depth Type, KO = 3/4 inch with cover. U.S. Brand	60	pcs.		
16	LL Condulet-3/4 inch in dia.. U.S. Brand	93	pcs.		
17	12mm x 400 mm x 4mm thick Cable Tie, black color (100 pcs. per pack)	3	packs		
18	Silicon sealant	24	tubes		
19	3/4 inch in dia. PVC Pipe x 10 long, Sch. 40 - Neltex Brand	400	pcs.		
20	2 inches in dia. PVC Pipe x 10 long, Sch. 40. - Neltex Brand	200	pcs.		
21	4 inches in dia. PVC Pipe x 10 long, Sch. 40. - Neltex Brand	60	pcs.		
22	1 inch in dia. Plastic Molding with adhesive - U.S. Brand Brand	130	pcs.		
23	3/4 inch in dia. PVC Elbow -Neltex Brand	200	pcs.		
24	1 inch in dia. Plastic molding Elbow - Neltex Brand	85	pcs.		
25	2 inches in dia. PVC Elbow -Neltex Brand	100	pcs.		
26	4 inches in dia. PVC Elbow -Neltex Brand	20	pcs.		

27	3/4 inch in dia. PVC box connector - Neltex Brand	240	pcs.		
28	2 inches in dia. PVC box connector - Neltex Brand	120	pcs.		
29	4 inches in dia. PVC box connector - Neltex Brand	16	pcs.		
30	3/4 inch in dia. Locknut	480	pcs.		
31	2 inches in dia. Locknut	240	pcs.		
32	4 inches in dia. Locknut	32	pcs.		
33	3/4 inch in dia. Bushing	240	pcs.		
34	2 inches in dia. Bushing	120	pcs.		
35	4 inches in dia. Bushing	16	pcs.		
36	3/4 inch in dia. Clamp - Malleable Tyoe	400	pcs.		
37	Assorted unitrust clamp, bracket, hanger, and box/pipe supports	1	lot		
38	Anchor Bolt - 3/8 inch in dia. X 2 inches long. U.S Brand	100	pcs.		
39	Anchor Bolt - 1/4 inch in dia. X 1-1/4 inches long. U.S Brand	120	pcs.		
40	Wall anchor - 5/16 inch x 1 inch in dia. Long, 100 pcs. box	5	boxes		
41	Consumable Materials	1	lot		
42	½ inch (13mm) nylon cord (1000 meters/Roll)	5	rolls		
43	Conceret Cement, Portland Brand	100	bags		
44	Sand	180	bags		
45	Gravel	350	bags		
46	12mm Round Bar x 20 feet long	30	bags		
47	10 mm Round Bar x 20 feet long	20	bags		
48	GI Wire	10	kilos		
49	1/4 inch Flywood, 4 feet x 8 feet long	8	pcs.		
50	Wood Lumber, 2 x 2 x 10 feet long.	24	pcs.		
51	3 inches long Ordinary Nail	5	kilos		
52	1 inch long Ordinary Nail	3	kilos		
53	QDE Paint - White, Boysen Brand	24	gal.		
54	Paint Brush, 2 inch wide	24	pcs.		
55	Paint Brush, 1 inch wide	24	pcs.		
56	Assorted Tinting color	10	pint		
57	Electrical Caution Tape - 3 inch Wide x 1000 feet per roll - U.S. Brand	4	rolls		
58	Stainless Plate Cover -Handhole, 17 inches x 17 inches x 1/4 inch Thickness	7	sets		
~~59~~	~~Power Outlet 120VAC & 220VAC with wires and conuits~~	~~1~~	~~lot~~		
~~60~~	~~PVC False Column (to cover the new riser 2 inches PVC Conduit/Pipe)~~	~~1~~	~~lot~~		A001
~~61~~	~~Restoration Cost for of all affected and damages to its original conditions/etc.~~	~~1~~	~~lot~~		
			TOTAL COST PHP		-