

<b>AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT</b>			1. CONTRACT ID CODE		PAGE OF PAGES 1   3		
2. AMENDMENT/MODIFICATION NO.  A001		3. EFFECTIVE DATE  February 9, 2012		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO. (If applicable)	
6. ISSUED BY  U.S. Embassy General Services Office Lange Voorhout 102			CODE  		7. ADMINISTERED BY (If other than Item 6) CODE		
				9a. AMENDMENT OF SOLICITATION NO.  S-NL800-12-Q-0002			
				9b. DATED (SEE ITEM 11) January 17, 2012			
				10a. MODIFICATION OF CONTRACT/ORDER NO.			
				10b. DATED (SEE ITEM 13)			
<b>11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS</b>							
<p>[ ] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [ ] is extended, [ x] is not extended</p> <p>Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning ____ 1__ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers.</p> <p><b>FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER.</b> If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.</p>							
<b>12. ACCOUNTING AND APPROPRIATION DATA (If required)</b>							
<b>13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.</b>							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. <b>IMPORTANT:</b> Contractor [ ] is not, [ ] is required to sign this document and return 0 copy to the issuing office.							
14. <b>DESCRIPTION OF AMENDMENT/MODIFICATION</b> (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is to delete the current Scope of Work and replace it with a new one.  Please see attached  FOR ALL INQUIRIES, PLEASE CONTACT MICHAEL FUNDAHN (31-70-3102210)  Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME OF CONTRACTING OFFICER  Michael Fundahn			
15B. NAME OF CONTRACTOR/OFFEROR  BY _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA  BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED	

Section B, Scope of Work is deleted in its entirety and replaced with the following:

## Scope of Work

### **B. Scope:**

This Statement of Work (SOW) addresses the acquisition and installation of replacement flooring (parquet) in (Tobias Asserlaan 4). The old (flooring type) will be removed and replaced with the new Merbau flooring.

### **Requirements:**

1. Contractor shall furnish all labor, materials and equipment necessary to perform the following:
  - a. Remove existing flooring and dispose of properly as described below.
  - b. Install new parquet flooring and all associated trim work needed.
  - c. The new parquet flooring shall be the same, style as the existing parquet flooring.
  - d. Contractor must provide color samples for approval prior to installation.

Area's equates to approximately XXX SM.

2. Site visits shall be scheduled by the Contracting Officer or designated representative. The Contractor shall be responsible for site investigation to determine conditions and quantity of materials required for each project.
3. Contractor shall provide all equipment and manpower required for complete delivery of all items to the site of installation. Contractor shall meet the shipment, unload, uncrate, and deliver the product(s) to the installation area.
4. ALL DAMAGE during or after a delivery and before final inspection, shall be the responsibility of the contractor and any damaged materials shall be replaced by the contractor at no additional cost to the U.S. Embassy

### **Waste Disposal:**

1. THE CONTRACTOR SHALL HAUL away from the project and legally dispose of all debris to an offsite location. If feasible, all waste should be disposed of at a carpet reclamation center.
2. SITE CLEAN-UP shall be performed daily.

### **Acceptance:**

1. The inspection/acceptance of the project shall be upon satisfactory demonstration of the project to the Contracting Officer. Demonstration and acceptance does not relieve the contractor from providing any other portion of this statement of work. The U.S. Embassy expects all contractor provided items to be in good working order even if not directly demonstrated (such as working electrical receptacles, burning lights, smooth action of drawers, etc.)

### **Scope of work:**

Replacement of wooden flooring (parquet) for the entry, hall family room and the piano room.

New parquet has to use Merbau panels for the existing flooring.

## *Central hall*

The contractor is responsible for measuring

According to current Merbau panels diagonally across the hall).

Strips 264 x 66 x 6 mm.

Including delivery and installation of a Wengé trim 10 mm, 71 mm tape Merbau, Wengé trim.

10 mm and Merbau locking strips 66 mm wide and 300 mm long.

Including delivery and installation of chipboard 8 mm on the leveled screed floor

Including sanding the floor and three layers of lacquer with Bona Traffic.

Includes demolishing and removing existing flooring.

Including leveling existing cement floor.

## Piano Room

The contractor is responsible for measuring

Merbau panels, laid right

(According to current Teak panels in the Piano Room.)

Panel size 260 x 260 mm , 4 strips per panel. Strips 260 x 65 x 6 mm.

Including delivery and installation of a Wengé trim 10 mm, 65 mm tape Merbau, Merbau locking strips 65 mm

Wide and 260 mm long, 65 mm tape Merbau and a Wengé trim 10 mm.

Including delivery and installation of chipboard 8 mm on the leveled screed floor.

Including sanding the floor and three layers of lacquer with Bona Traffic.

Includes demolishing and removing existing tapis Teak parquet panels including between floor.

Including leveling existing cement floor.

Includes entrance Piano Room to Petit Salon. The bands and piping running through here in both areas.

## Family room

The contractor is responsible for measuring.

Family Room

Merbau Panels lay diagonally.

(According to current American Walnut panels diagonally across the hall).

Panel size 264 x 264 mm, 4 strips per panel. Strips 264 x 66 x 6 mm.

Including delivery and installation of a Wengé trim 10 mm, 71 mm tape Merbau, Wengé trim

10 mm and Merbau locking strips 66 mm wide and 300 mm long.

Including delivery and installation of chipboard 8 mm on the leveled screed floor without cables.

Including sanding the floor and three layers of lacquer with Bona Traffic.

Includes demolishing and removing existing flooring.

Including leveling existing cement floor.

Includes Family Room entrance to Central Hall. Merbau strips 71 mm wide. Total of 426 x 1160 mm.

= 0.48 m<sup>2</sup> .

Includes Family Room entrance to Hallway. Merbau strips 66 mm wide and 264 long.

The contractor is responsible for measuring.

There will be no doorstep on the Floor between the rooms, the new flooring will continue between the rooms (same patron and type)