



*Embassy of the United States of America  
Muscat, Oman*

## SCOPE OF WORK

DATE: April 23, 2014

***PROJECT: Renovate 4 toilets at GOH X7007***

***LOCATION: Road 15 House 1, MQ.***

### ***1. PROJECT DESCRIPTION***

- a. Renovate 5 toilets in house X7007

### ***3. PROJECT SCHEDULE & WORKERS.***

- a. Work days to be coordinated with Facilities Manager( FM)/Contracting Officer's Representative ( COR)
- b. Contractor should submit proposed work schedule and time line for FM's/ COR's approval.
- c. Work hours will be from 0800 to 17:00, Sunday through Thursday.

The following points of the project must be approved prior to the contractor proceeding to the next phase.

- a. Approval of material selection.
- b. Site inspection after demolition
- c. Site inspection during each phase of work.

5. QUALITY CONTROL

- a. A site supervisor that has a minimal knowledge of English must be present at all times.
- b. Site supervisor will ensure the material is not damaged prior to or during installation and that standard industry practices as defined in the International Building Code, are followed at all times.
- c. A final inspection will be held with the Embassy and the site supervisor to inspect for quality of the finished works.

6. SAFETY

- a. Site supervisor will ensure that all equipment used during the project is in safe operating condition. All personnel on the job site will be given the appropriate safety equipment. The Embassy reserves the right to stop the work if any unsafe conditions are found.
- b. All electrical equipment such as drills, grinding, buffing machines and any extension cords must be properly grounded and be free from any defect in the insulation
- c. All ladders/scaffoldings will be in good condition and used in a proper manner.

7. SECURITY

- a. A list of all personnel working on the project along with Identification numbers must be submitted to the embassy no later than 5 working days prior to the beginning of actual starting date of the project.

Scope of works for renovate 5 bathrooms at X7007

1. Work area shall be cleaned of all debris at the end of each workday.
2. The contractor should provide all required tools, materials and safety equipment to complete the project.
3. After hours and weekend work may be required. The Facility Manager will determine.
4. All existing surface area that will not be replaced shall be protected from damage by the contractor. Protection materials provided by the contractor.
5. Only those materials approved by the Facility Manager will be used. Contractor must provide samples, at the request of Facility Manager.
6. Contractor must make a site visit to check the accuracy of measurements.
7. Local civil construction standards shall be met for all civil works.
8. When replacing copper, PVC and traps, all piping must be concealed in the walls, both outside and inside piping.
9. Check all pipes, fittings and joints for leaks and conduct a water pressure test 160-PSI for 24 hours.
10. Wrap all concealed copper pipes with denso tape.
11. All sanitary fittings and accessories shall be as specified in the bill of materials.
12. All sanitary fittings shall be of water saving type & all other sanitary equipment like shower tray & sink shall be white color.
13. The exhaust fan should be timer controlled or with an occupancy sensor.
14. All material shall be provided by contractor, including paint.
15. All hot and cold water pipes shall be copper with welded joints and should be tested for minimum 160 PSI water pressure.
16. Ensure all underground drainage PVC pipe from toilet up to the manhole in the extreme end of the property are clean and clear and clean all manholes.
17. Dispose of trash in a proper disposal facility

Schedule of work, Renovate Toilets

**Item I Entrance toilet**

18. Replace all pipes, valves, wall & floor tiles, sanitary equipment & accessories, floor drain, exhaust fan, light fixtures and medicine cabinets/mirror. Replace floor drain S/Steel type press & push closable type.
19. Remove all sanitary fittings, accessories, damaged wall & floor tiles in the toilet room.
20. Remove all damaged existing pipes in the bathroom and up to the roof and the in the manholes.
21. Replace/relocate the water heater exterior wall/roof of the toilet
22. Install new copper hot and cold pipes, fittings and PVC drainage lines and traps.
23. Replace 3sqm of existing floor tile.
24. Replace 12 sqm of existing wall tile.

25. Bright white non staining grouting shall be used on wall tiles
26. Replace toilet with water saver toilet with dual flush mechanism.
27. Supply and install a vanity basin with cabinet underneath.
28. Install contractor provided GROHE good quality water saver faucet
29. Install one shelf under mirror 60cm long x 10cm wide made of ceramic.
30. Install ceramic wall and floor tiles as approved.
31. Walls above tile shall be painted with primer and two coats of Sadolin 88 interior paint, beige.
32. Replace exhaust fan with timer control or with an occupancy sensor.
33. Replace ceiling & wall light with energy saver lamps ( CFL or LED).
34. Ceiling shall be painted with Sadolin88 white matte finish, two coats.
35. Test and commission all equipment.
36. Clean the area.
37. Dispose of trash in a proper disposal facility.

#### Item II Guest bedroom toilet next to kitchen

38. Relocate the water heater exterior to the toilet /roof, with concealed piping.
39. Replace the existing sink with vanity basin type and cabinets underneath.
40. Install shower enclosure with tempered glass enclosure.
41. Replace floor drain S/Steel type press & push closable type.
42. Regrout floor tiles.
43. Bright white non staining grouting shall be used on wall & floor tiles
44. Replace existing toilet with water saver toilet with dual flush mechanism.
45. Install contractor provided GROHE good quality water saver faucet
46. Ceiling shall be painted with Sadolin88 white matte finish, two coats.
47. Walls above tile shall be painted with primer and two coats of Sadolin 88 interior paint.
48. Replace exhaust fan with timer control or with an occupancy sensor
49. Test and commission all equipment.
50. Clean the area.

#### Item III Second bedroom toilet next to Hallway

51. Relocate the water heater exterior to the toilet /roof, with concealed piping.
52. Replace the existing sink with vanity basin type and cabinets underneath.
53. Install bathtub enclosure with tempered glass enclosure.
54. Replace floor drain S/Steel type press & push closable type.
55. Regrout floor tiles.
56. Bright white non staining grouting shall be used on wall & floor tiles
57. Replace existing toilet with water saver toilet with dual flush mechanism.
58. Install contractor provided GROHE good quality water saver faucet

59. Ceiling shall be painted with Sadolin88 white matte finish, two coats.
60. Walls above tile shall be painted with primer and two coats of Sadolin 88 interior paint.
61. Replace exhaust fan with timer control or with an occupancy sensor
62. Test and commission all equipment.
63. Clean the area.

Item IV: Master bedroom toilet.

64. Replace the existing sink with vanity basin type and cabinets underneath.
65. Install bath tub enclosure with tempered glass enclosure.
66. Replace floor drain S/Steel type press & push closable type.
67. Regrout floor tiles.
68. Bright white non staining grouting shall be used on wall & floor tiles
69. Replace existing toilet with water saver toilet with dual flush mechanism.
70. Install contractor provided GROHE good quality water saver faucet
71. Ceiling shall be painted with Sadolin88 white matte finish, two coats.
72. Walls above tile shall be painted with primer and two coats of Sadolin 88 interior paint.
73. Replace exhaust fan with timer control or with an occupancy sensor
74. Test and commission all equipment.
75. Clean the area.

Item V: Maid's Quarter toilet.

76. Replace all pipes, valves, wall & floor tiles, sanitary equipment & accessories, floor drain, exhaust fan, light fixtures and medicine cabinets/mirror. Replace floor drain S/Steel type press & push closable type.
77. Replace defective toilet door & door frame.
78. Remove all sanitary fittings, accessories, damaged wall & floor tiles in the toilet room.
79. Remove all damaged existing pipes in the bathroom and up to the roof and the in the manholes.
80. Replace/relocate the water heater exterior wall/roof of the toilet
81. Install new copper hot and cold pipes, fittings and PVC drainage lines and traps.
82. Replace 3sqm of existing floor tile.
83. Replace 12 sqm of existing wall tile.
84. Bright white non staining grouting shall be used on wall tiles
85. Replace toilet with water saver toilet with dual flush mechanism.
86. Replace the existing sink.
87. Install contractor provided GROHE good quality water saver faucet
88. Install one shelf under mirror 60cm long x 10cm wide made of ceramic.
89. Install ceramic wall and floor tiles as approved.

90. Walls above tile shall be painted with primer and two coats of Sadolin 88 interior paint, beige.
91. Replace exhaust fan with timer control or with an occupancy sensor.
92. Replace ceiling & wall light with energy saver lamps ( CFL or LED).
93. Ceiling shall be painted with Sadolin88 white matte finish, two coats.
94. Test and commission all equipment.
95. Clean the area.

Item VI Repair bedroom floor & install ceramic floor tiles 9.5 SQM approx...

**Itemized pricing shall be done for each item & the cost shall be lump sum.**