

Fitting of a Refrigerated Platform for Container Check. This consist on the welding of 2 refrigerated containers as follows:

Elimination of 22 indoor and outdoor side panels (2 containers)

2 side perforations on the welded container (2.50 Mt x 2.50 Mt)

1 back perforation (1mt x 2mt)

Manufacturing of a shed cold protection

Installation of lateral frames and doors

Installation of back frames and doors

Steel sheet 3mm caliber (12mt x 4.88mt)

Internal lighting (6 lamps)

6 mounts for the container 4"x1/4"

Polyurethane insulation and steel sheets screwed in the union lines of both containers

See attached graphic for referral