

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	Page 1 of 3
2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE 06/22/2015	4. REQUISITION/PURCHASE REQ. NO. PR4177966-A002	5. PROJECT NO. (If applicable)	
6. ISSUED BY AMERICAN EMBASSY PANAMA CITY APARTADO 0816-02561, ATTN: GSO PANAMA, PANAMA	CODE PM070	7. ADMINISTERED BY (If other than Item 6) CODE AMERICAN EMBASSY PANAMA CITY APARTADO 0816-02561, ATTN: GSO PANAMA, PANAMA		
8. NAME AND ADDRESS OF CONTRACTOR (NO., street, city, county, State, and ZIP Code) NOVENDOR UNITED STATES		X	9a. AMENDMENT OF SOLICITATION NO. SPM07015Q0030	
			9b. DATED (SEE ITEM 11)	
			10a. MODIFICATION OF CONTRACT/ORDER NO.	
			10b. DATED (SEE ITEM 13)	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS				
<p>X The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers _ is extended, x is not extended Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning Error! Unknown document property name. copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.</p>				
12. ACCOUNTING AND APPROPRIATION DATA (If required)				
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.				
—	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.			
—	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)			
—	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:			
—	D. OTHER (Specify type of modification and authority)			
E. IMPORTANT: Contractor _ is not, _ is required to sign this document and return copies to the issuing office.				
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is replace Scope of Work . See attached				
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.				
15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME OF CONTRACTING OFFICER IADONNA SALES		
15B. NAME OF CONTRACTOR/OFFEROR BY _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA, BY (Signature of Contracting Officer)		16C. DATE SIGNED 06/18/2015

1. Please delete Attachment #2 Scope of Work and replace with:

ATTACHMENT #2 – SCOPE OF WORK

Project: CMR Electrical Phase One

Location: Manuel Hurtado Street, La Cresta, Bella Vista Panama City, Republic of Panama.

Description: Install new generator pad, duct bank and fuel line.

INTENT – Requirements in this SOW serve as direction for development and delivery of a complete technical proposal, construction documents, and construction by a contractor. The work shall be in accordance with international professional standards of skill, care and diligence.

1.0 Proposal:

- 1.1 Overview – This is Phase One of the multiple phased projects. This includes preparation work for the installation of a new generator in a new location.
- 1.2 Project Description – Install concrete pad, concrete vault to connect to adjacent underground utilities conduit and run a new fuel line.
- 1.3 Government furnished material (GFM) – None

“The contractor will provide restricted and control demolition work area. All debris will be groups together or removed from the property daily. Dirt and rubble can be placed in a provided location until a large enough quantity is buildup”.

Ensure the construction site is kept neat and orderly by the end of the work day.

The contractor shall cover all the floor areas with a heavy troponin to protect the floor. In the area where work is being performed, floor protection will remain in place where routine foot traffic passes through until the project is completed.

2.0 Demolition work:

- 2.1 Excavate for the 9’x17’x8” concrete pad.
- 2.2 Excavate for underground concrete vault 4’x4’x3’
- 2.3 Excavate for underground 6”PVC conduit.
- 2.4 Excavate for underground fuel line.
- 2.5 Excavate for underground control conduit, from the new generator pad the the location for the ATS.

3.0 Installation work: (repairs)

- 3.1 Install new concrete pad 9’x17’x 8”.
- 3.2 Install new underground concrete vault.
- 3.3 Install 6” PVC pipe as needed to connect the new vault, and generator to the existing underground conduit.
- 3.4 Install double walled fuel supply line with 3/4” inside diameter. The fuel line shall be rated for direct burial and fuel. The fuel line shall run from inside the existing fuel tank room to the new generator pad. Both end will be capped.
- 3.5 Install 1 ½” shc 40 PVC conduit underground between the new generator pad and electrical room, to connect into the generator and ATS.

4.0 Life Safety Protection:

- 4.1 The Contractor shall ensure that the works are carried out in accordance with safety and health regulations with particular attention given to: personal protective equipment, guard rails, scaffolding, electric leads and access ladders. The work shall meet OSHA standards - <http://www.osha.gov/> and Safety and Health Requirement Manual, EM 385-1-1.
- 4.2 The Contractor shall not, at any time, leave work in an unsafe condition or any condition that might cause injury to personnel, damage to existing work, plant or equipment but shall continue that work until it is at a safe stage.
- 4.3 As some painting will be in stairwell, the contractor shall use fixed scaffolding in the stairwells. Paint each stairwell one at a time. The stairwell being painted will be closed.
- 4.4 The Contractor shall have COR approved fall protection for scaffolding workers.

5.0 Project Requirements:

- 5.1 Design – NA USG provided
- 5.2 Construction –

- 5.2.1 The Contractor shall carry out the construction, as described in items 1.0, 2.0 and 3.0 above, in accordance with the approved final Construction Documents - manage, administer, supervise and inspect the construction. The coordination and supervision of all work shall be the responsibility of the Contractor. All work has to be executed with minimal disruption to the traffic and operations on work site.
 - 5.2.2 Provide a detailed Construction Schedule with sufficient detail to describe each key construction activity.
 - 5.2.3 The USG will have the right to access the construction site at all times inspecting the project construction in its entirety. Access will be coordinated with Contractor who is responsible for compliance with embassy security rules and regulations.
 - 5.2.4 During construction hold meetings with the COR for progress reporting and coordination.
 - 5.3 Coordination – The Contractor shall coordinate the project requirements with Embassy Contracting Officer’s Representative (COR). COR for this project will be Facility Manager.
 - 5.3.1 Toilet – Will be defined by the COR.
 - 5.3.2 Break area – Will be defined by the COR.
 - 5.4 Catalogue Cut Sheets - Provide bound copies of manufacturer’s catalogue cut sheets for all equipment and materials, for review.
- 6.0 Project Deliverables:
- 6.1 Architectural – NA
 - 6.2 Interior Design– NA
 - 6.3 Structural – NA
 - 6.4 Mechanical- NA
 - 6.5 Electrical – NA
 - 6.6 Telecommunications – NA
 - 6.7 Life Safety Fire Protection – Immediately remove debris immediately from demo work off site and do not store debris on site.
 - 6.8 Project Schedule – Provide a detailed project schedule with cost-loaded and other sufficient detail for all construction activity.
- 7.0 Submittals:
- 7.1 Provide submittals that are complete, coordinated and consistent. OBO comments on each submittal shall be resolved prior to making the next submittal. Any of the work found to be unsatisfactory by the COR, shall be rectified.
 - 7.2 Thoroughly check and coordinate all project submissions to the USG. Deficiencies, ambiguities, conflicts, and inconsistencies shall be rectified.
 - 7.3 Written Documents - The deliverable format is A4 bound paper copy. Deliver all word processing in Microsoft Word; spreadsheets in Microsoft Excel; and schedules in Microsoft Project.
 - 7.4 Drawings - All drawings are to be delivered in hard copy. Drawings shall be submitted in A4.
- 8.0 Schedules of Deliverables:
- 8.1 Materials submittals 5 days after NTP,
 - 8.2 Construction Substantial Completion 10 days after construction NTP,
 - 8.3 Punch List 3 days after Agreement.

