

FAC
US EMBASSY LIMA PERU

PROJECT: MSGQ basement Repair
SECTION: FAC

PRICE SCHEDULE BREAKDOWN

ITEM	DESCRIPTION	UNIT	QUANTITY	Cost US \$	TOTAL US \$
1.00	Mobilization	Glb	1		
2.00	crew insurance	Glb	1		
3.00	discard material removal	Glb	1		
4.00	ACAD drawing modifications	Glb			
5.00	Office	Glb			
	4 "Sewer replacement with PAVCO vintuit PVC pipe, including two collection box.				
	Replace plaster in walls affected by humidity				
	Remove floor affected by humidity				
	Provision and installation ceramic tiles				
	wooden door replacement				
	Electrical installations light fixtures outlets and wiring.				
	Interior painting oleo based paint two coats				
	Door painting with black enamel two coats				
	Mirrors replacements				
6.00	Dressing	Glb			
	Demolition/Removal wall tiles and floors				
	Provision and installation of ceramic tiles				
	Installation of fixtures toilet and sink				
	Wall partitions according to drawings, including electrical boxes				
	New wood doors and frames				
	Refinish to existing doors				
	Electrical installations for light fixtures outlets and wiring.				
	Exhaust fan system installation with sensors				
	Plumbing installations				
	Interior painting oleo based paint two coats				
	Mirrors replacement				
	faucetts and mixer replacements				
7.00	Guest bathroom	Glb	1		
	Demolition/Removal wall tiles and floors				
	Provision and installation of ceramic tiles				
	Installation of fixtures toilet and sinks				
	Provision and granite counter for sink				
	Wall partitions according to drawings, including electrical boxes				
	New wood doors and frames				
	Refinish to existing doors				
	Electrical installations for light fixtures outlets and wiring.				
	Plumbing installations				
	Interior painting oleo based paint two coats				
	Mirrors replacement				
	faucetts and mixer replacements				
8.00	Guards Bathroom	Glb	1		
	Demolition/Removal wall tiles and floors				
	Provision and installation of ceramic tiles				
	Installation of fixtures toilet and sinks				
	Refinish to existing doors				
	Plumbing installations				
	Interior painting oleo based paint two coats				
	Mirrors replacement				
	faucetts and mixer replacements				
9.00	Pool Bathrooms	Glb	1		
	Demolition/Removal wall tiles and floors				
	Provision and installation of ceramic tiles				
	Installation of fixtures toilet and sinks				
	Refinish to existing doors				
	Electrical installations for hand dryer.				

