U.S. Embassy
686 Old Bagamoyo Road
Dar Es Salaam, Tanzania

12 June, 2015.

REQUEST FOR QUOTATION for ***PR 4415659 Installation of New underground water pipe line with electric pump.***
Dear Vendor,

The Embassy of the United States of America invites you to submit your quotation for the services shown below in a Scope of work.

A Site visit will be held at Wednesday June 18, 2015 at 10:00am. For access, please send your name via an e mail at least two days ahead of time to **tungulim@state.gov.**

Your quotation must be submitted by ***1100 hours local time on Thursday 25 June, 2015.***

If you send a paper quotation (on which our PR 4415659 is clearly stated), it must be in a sealed envelope marked as follow.

GSO-U.S EMBASSY CONTRACTING OFFICER
Quotation Enclosed
PR 4415659 for Roof Replacement.
686 Old Bagamoyo Road Msasani,
Dar es salaam, Tanzania.

The electronic address for submission is darprocurementbid@state.gov.

- On the e-mail subject line, state that the submission is for ***PR 4415659 for Roof Replacement.***
- On your attached quotation, state that the quotation is for ***PR 4415659 for Roof Replacement.***

The US Government intends to purchase the lowest priced technically acceptable product or service.

All vendors receiving awards over $25,000 must be registered in the System for Award Management (SAM). When submitting your bids, write your SAM Registration information directly and clearly on your quotation.

We encourage all vendors which may bid either on this solicitation or in the future to start now and complete the SAM registration process. Registration will make the award process move much more smoothly and quickly. The registration process is not difficult, provided all instructions are followed carefully. Please see our Embassy Contract Opportunities web page for details or call us if you have questions

Any questions regarding this Request for Quotation must be directed to the Contracting Officer +255-22-229-4121 during office hours.

Sincerely,

The Contracting Officer

Scope of work

LOCATION: American Club – U.S Embassy Dar Es Salaam; 686 Old Bagamoyo Road.

Supply and install new underground water pipe line for the support compound – 300 running meters

From Existing underground water tank at the entrance to the over ground tank farm at the back complete with electric water pump set.

SCOPE OF WORKS:

1. Prepare and excavate appropriate trench /channel for water pipe installation. The trench shall be minimum 500mm deep to receive the pipes and accessories.
2. Provide a protective layer bed of river sand in the trench and Install high pressure water pipe line consisting of 2inches H.D.P.E. coil pipe Class C complete with all appropriate fittings and connections.
3. Also, install in the same trench appropriate power control cable for the pump control.
4. After pressures testing the completed pipe line system, back fill firstly with river sand, lay warning tape indicating Water Pipe Line, and finally the normal earth backfill. Compact and make good the trenched area.
5. At the existing underground water tank, supply and install appropriate standard submersible electric water pump capable of pumping water to the tank farm 300metrs away. The pump set shall be complete with controls and floats for automatic start on when the tank farm calls for water and shuts down when the tanks are full. Also, it should have dry run protection when the source of water is low.
6. Provide a simple canopy / roof over the pump controls to protect against rain and sun.
7. Test and commission the completed water supply system and hand over with appropriate paper works to the Embassy.
8. Demobilize and clear all the debris from site.

NOTES:

1. The Contractor shall furnish and supply all materials required by this scope of work.
2. The contractor should survey the property and verify the work required against the scope of works to determine if any discrepancies exist. The contractor shall be responsible for any errors, which might have been avoided by such a survey/review.
3. The contract will be a firm fixed price contract payable entirely in the currency indicated in the bid. No additional sums will be payable on account of any escalation in the cost of materials, equipment or labor, or because of the contractor's failure to properly estimate or accurately predict the cost or difficulty of achieving the results required by this scope of works.

END