

US Embassy
686 Old Bagamoyo Road
Dar Es Salaam, Tanzania

July 30, 2014

REQUEST FOR QUOTATION for **PR3519000 64kW Modular UPS**

Dear Vendor,

The Embassy of the United States of America invites you to submit your quotation for the products or services shown below.

If you would like to submit a quotation, please provide a pro-forma invoice.

Note that we will accept quotations for products or services with certifiably equivalent specifications. We require technicians to be located locally and to be factory trained or certified.

Your pro-forma invoice (on which **PR3519000 64kW Modular UPS** is clearly stated) must be received by **1100 hours local time on August 21, 2014** in a sealed envelope marked as follows.

Contracting Officer
Quotation Enclosed
PR3519000 64kW Modular UPS
686 Old Bagamoyo Road Msasani
Dar es Salaam, Tanzania

An alternative address for submission is darprocurementbid@state.gov.

- On the e-mail's subject line, state that the submission is for **PR3519000 64kW Modular UPS**
- On your attached proforma, state that the proforma is for **PR3519000 64kW Modular UPS**

The US Government intends to purchase the lowest priced technically acceptable product or service.

All vendors receiving awards over \$25,000 must be registered in SAM.

We encourage all vendors which may bid either on this solicitation or in the future to start now and complete the SAM registration process. Registration will make the award process move much more smoothly and quickly. The registration process is not difficult, provided all instructions are followed carefully. Please see our Embassy Contract Opportunities web page for details or call us if you have questions

Any questions regarding this Request for Quotation must be directed to the Procurement Section +255-22-229-4138 during office hours.

Sincerely,

The Contracting Officer

Dar es Salaam - US Embassy – CDC
Modular UPS
(CDC Tanzania 64kW UPS)
PR3519000 64kW Modular UPS

Product must be delivered within 6 weeks after order is placed

CDC Tanzania wishes to purchase one Uninterruptible Power Supply Unit (UPS) for providing backup power to its Information technology Infrastructure. Supplied equipment must be able to handle widely varying quality and levels of electricity arriving from the municipal supplier.

We request one Symmetra PX model number SY64K96H which is manufactured by American Power Conversion (APC). Major features, but not necessarily all features, are listed below.

Note that we will accept equipment with certifiably equivalent specifications as are found in the listed part. It is the responsibility of the vendor to ensure that the supplied equipment meets all the requirements and has, at a minimum, all features of the requested part.

Regardless of the manufacturer, support parts and factory trained and certified technicians must be available in Dar Es Salaam, Tanzania.

Major Features

- Both UPS and batteries must be in modular configuration mounted in cabinets.
- The UPS must be delivered configured as 64kW but scalable to 96kW with Integrated Modular Distribution.
- The UPS must be delivered with installed battery modules capable of providing run time of at least 50 minutes at 64kW load.
- The UPS must have an LCD Control panel that provides status of the equipment at real time.
- The UPS must have a network management card with environmental monitoring and out of band management.
- The UPS must be equipped with built-in hot-swappable static bypass switch capable of transferring the load to utility power without interruption in case of heavy load or faulty conditions.
- A minimum of one (1) year performance warranty and service agreement on the UPS and batteries.

Period of Performance (Maintenance) – 12 months (1 year) after delivery and installation of product

Scope of Work Details

- Supply of the modular UPS to the CDC Tanzania office at 2448 Luthuli Street, Dar Es Salaam, Tanzania
- Supply of battery frames and modules capable of providing a minimum of 50 minutes run time at 64kW load.
- Installation and configuration of the modular UPS.
- Installation and configuration of the battery frame and battery modules.
- Provision of all equipment and material needed for installation and testing of the UPS.
- Proper termination of all cables required to connect the UPS to the mains and Generator and also to the server room and computer power outlets.
- Configure UPS network management feature to automatically send alerts via SMS/Email to designated

staff.

- Synchronization of the UPS with the generator and the mains
- Testing and commissioning the new modular UPS installation
- Removal of the existing APC SL60KH Silcon UPS, its battery compartments and cabling
- Proper disposal of the existing APC SL60KH Silcon UPS

Price

- Interested vendors should provide quote for the following. All costs should be quoted on separate line items and not combined.
 - Cost of the product
 - *Shipping*
 - Installation
 - Commissioning of a new modular UPS
 - Removal of the existing UPS.

Shipping

In your quotation, please include a line item for door-to-door shipment to the following location.

CDC Tanzania
2448 Luthuli Street
Dar Es Salaam, Tanzania