

U.S. Embassy
686 Old Bagamoyo Road
Dar Es Salaam, Tanzania

August 14, 2014

REQUEST FOR QUOTATION for **PR3591043 Renovate Wall 357**

Dear Vendor,

The Embassy of the United States of America invites you to submit your quotation for the products or services shown below.

A site visit will be held at **1300 on August 25, 2014**. For access, please send an e-mail at least two days ahead of time to MarealleRA@state.gov.

Your quotation must be submitted by **1100 hours local time on September 15, 2014**.

The electronic address for submission is darprocurementbid@state.gov.

- On the e-mail's subject line, state that the submission is for **PR3591043 Renovate Wall 357**
- On your attached proforma, state that the proforma is for **PR3591043 Renovate Wall 357**

The US Government intends to purchase the lowest priced technically acceptable product or service.

All vendors receiving awards over \$25,000 must be registered in SAM.

We encourage all vendors which may bid either on this solicitation or in the future to start now and complete the SAM registration process. Registration will make the award process move much more smoothly and quickly. The registration process is not difficult, provided all instructions are followed carefully. Please see our Embassy Contract Opportunities web page for details or call us if you have questions

Any questions regarding this Request for Quotation must be directed to the Procurement Section +255-22-229-4138 during office hours.

Sincerely,

The Contracting Officer

U.S. Embassy

PR3591043 Renovate Wall 357

Scope of Work

TEMPORARY BARRICADES

The contractor shall protect the work as it proceeds, protect the area which is next to the construction, and protect the materials and components from damage and deterioration. Special consideration should be given to protecting sensitive areas such as hallways, entrances, walls, floors and carpeted areas from dust and construction activities.

The contractor shall provide barricades as required to protect natural resources, site improvements, existing property, adjacent property, and personnel.

Where pedestrian traffic moves through or adjacent to the work area, the contractor shall provide necessary guardrails and barricades to protect pedestrians and to prevent pedestrian access to work areas. Remove guardrails and barricades at completion of construction.

EXECUTION AND CLOSEOUT REQUIREMENTS

Final Completion

After completion of the work, the contractor shall make an appointment with COR for inspection and final acceptance with the signature of the COR. The work site and related areas must be in a clean and tidy condition.

Where there are visible cracks which are confirmed during the site visit, the Contractor shall remove that portion of the wall and build it from the ground up following this procedure:

- Contractor to dig a 50 X 50 Cm trench along the wall base before erection of new wall.
- Contractor to lay 10 cm of sand as first layer on the trench.
- Contractor to lay 10 cm Or 6 Inch of concrete on top of the layer of sand.
- Contractor to look on the existing wall for resemblance and at least lay horizontally lay 3 courses of 6 X 9 X 18 inches solid bricks separated by a reinforced concrete pillars after every 4 Meters gap. The round bars on the concrete pillars should be 16mm²
- Contractor will vertically lay 6 X 9 X 18 Inches solid bricks to the height that resembles the existing wall separated by a reinforced concrete pillars after every 4 Meters gap and then do plastering on the wall.
- Contractor shall provide/repair perimeter lights on top of the perimeter wall at approximately 4 meters gap to provide illumination. Contractor shall provide samples of three varieties of perimeter lights, preferably non corrosive, before work begins. The COR will make a choice.
- Contractor shall paint wall using bonding sealant, apply coats of acrylic primer and finalize with white plastic coating paint or weather guard.
- On the spikes the contractor shall apply two coats of zinc chromet primer as primer and then finalize with minimum two coats of black epoxy coating paint or hammer rite finish coating.
- Fabricate a sliding gate to match the height of the wall.
- Contractor shall remove and clear upon completion, all temporary buildings, construction debris, reinstate services disturbed and leave work site clean and tidy.