

U.S. Embassy  
686 Old Bagamoyo Road  
Dar Es Salaam, Tanzania  
August 25, 2014

REQUEST FOR QUOTATION for PR3664450 - LOC 1351 Msasani Windows and Driveway repairs

Dear Vendor,

The Embassy of the United States of America invites you to submit your quotation for the products or services shown below.

Your quotation must be submitted by **1100 hours local time on September 22, 2014**.

A site visit has been scheduled for September 4, 2014 at 1000hrs.

The electronic address for submission is [darprocurementbid@state.gov](mailto:darprocurementbid@state.gov).

- On the e-mail's subject line, state that the submission is for – PR3664450 - LOC 1351 Windows and Driveway repairs
- On your attached proforma, state that the proforma is for – PR3664450 - LOC 1351 Windows and Driveway repairs

The US Government intends to purchase the lowest priced technically acceptable product or service.

All vendors receiving awards over \$25,000 must be registered in SAM.

We encourage all vendors which may bid either on this solicitation or in the future to start now and complete the SAM registration process. Registration will make the award process move much more smoothly and quickly. The registration process is not difficult, provided all instructions are followed carefully. Please see our Embassy Contract Opportunities web page for details or call us if you have questions

Any questions regarding this Request for Quotation must be directed to the Procurement Section +255-22-229-4138 during office hours.

Sincerely,

The Contracting Officer

# U.S. Embassy

PR 3664450 - LOC 1351 Windows and Driveway repairs

## Location 1351

### Tasks involved

1. UPVC WINDOWS INSTALLATION
2. PAVEMENT BLOCKS INSTALLATION

### UPVC WINDOWS INSTALLATION. 28 WINDOWS INVOLVED

1. Replace all existing windows and transoms in main house with white UPVC double glass windows. Install new UPVC window according to specification. New double glass window shall be 5mm thick clear glass with minimum of 6 mm vacuum gap. The minimum thickness for UPVC extrusion profile shall be 2.5mm. Provide window schedule shop drawing that conforms to the site condition to the COR for approval prior to the commencement of the work. Submit window schedule shop drawing within a week of the contract issuance.
2. Install double 5mm glass with minimum 6mm vacuum gap complete with accessories. All accessories, such as: lever handle, locking system, hinges, drainage system in window and rubbers, have to be prepared and installed in U-PVC workshop.

### PAVEMENT BLOCKS INSTALLATION

Cement pavement blocks are required to replace disheveled/severely cracked/completely broken down unrepairable cement drive way .

The actual area to be paved has to be measured by visiting the site in order to get details. The soil has to be excavated. In order to calculate the soil to be excavated the below

Calculate the total excavation depth with this formula:

- Base compacted murrum: 10-15 Centimetres
- Sand bedding: 5 Centimetres
- Paver thickness:10 Centimetres
- Total of above: 25-30 Centimetres.

Paving stones should be laid diagonally.

Masonry sand, can be used to complete the filling of the joints after the initial compaction and sweeping with concrete sand.

Granite precast curbs have to be provided on the side of the roadway.

## WORK RESTRICTIONS

### Protection

Contractor will keep the project area cleaned and remove debris from project site at the end of each day. Loitering around the project site is not permitted.

Contractor shall be responsible for protecting U.S. Government property on site from damage, scratch, dust, water, fire or theft, and ensure caution to prevent accidents caused by various work. Install proper warning signs and protection to the site.

Contractor's operations may not cause disruption of site activities. Contractor's operations shall not generate disagreeable environmental effects, including the emission of noise, fumes, or other emanations. Construction debris shall be monitored at all times. Visual or audible disturbances shall be kept to a minimum, and any work progress, which might cause such disturbances shall be discussed with the COR in advance.

Contractor will provide labor, materials, equipment, and other necessary items required and related to the completion of the project.

All fixtures removed from the house, must be returned to the U.S Embassy's warehouse.