

Request For Quote Number: SMT85015Q001

Dated: July 23, 2015

Attachment .

General Specifications - Scope of Work

1. The contractor shall provide all labor and material to dismantle approximately 200 linear meters x 1.22 meter high of railings. All vertical poles, being grouted into the ground, will be left on site and can be treated separately.
2. The contractor shall provide all labor and material to remove existing paint and rust on all railings, panels, and vertical poles.
3. The contractor should treat all metals with a galvanic coating with a minimum of 99% pure zinc @ 75 – 100 microns.
4. The contractor shall provide a finishing coat of paint in color RAL 7035 for all railings and vertical poles.
5. The contractor shall re-install all railings in the same location that they were removed from.
6. The contractor shall use stainless steel fixtures, to include but not limited to hinges, screws, nuts, bolts, etc.