

## SCOPE OF WORK

## Repairs at US Government Owned Residence

1. Repair by replacement of the existing heating pipes. Remove the existing pipes starting from the boiler room to every single space heater. Install new copper pipes and distribution valves as per the attached specification of materials. Restore the concrete surface of the floors after completion of the work. Before restoring the floors provide 72 hours water test of the new pipe lines. No joints are allowed in floors or walls. If a joint has to be made in wall a revision opening to be provided for future inspection and repair. All copper joints to be with brazing. Remove the metal bars from the floors before installing the new laminated floors.
2. Specifications of the materials:

[illegible]

FY 2015

3. Replace laminated floors in the house. Install the new floors after the water test of the heating system was completed and the patched floors are completely dry. The total area of the laminated floors and stairs to be replaced is 150 sq. m. The quality of the laminated material for

the new laminated floors to meet grade 31 for rigidity and thickness of the elements not less than 8mm. The contractor shall provide new padding of 5 mm. and new baseboards for all rooms and stairs. The type and the color of the laminated floors and baseboards to be approved by the Embassy before being purchased by the contractor.

4. White latex paint for all the walls and ceilings after:

- Remove all nails from the walls.
- remove old plaster and make a new one on all walls and ceilings, total area to be repaired is 568 sq.m.
- after applying the new gypsum plaster, apply one coat of prime before latex paint. The prime coat to be applied after the plaster is dry, not earlier than 7 days after applying the new gypsum plaster and water content less than 10%.
- White latex paint for 568 sq.m. of walls and ceilings. The latex paint to meet the following standard: TC-AK-E001 and to be approved by Embassy representative:

ПОКАЗАТЕЛИ	Стойност съгл. ТС – АК – Е001	Резултат от анализа
1. Външен вид.	хомогенна гъста до тиксотропна маса	...ОТГОВАРЯ..
2. Цвят на филма.	по еталон на фирмата	.....ОТГОВАРЯ...
3 Вискозитет по ВЗ-4 при 20°C в сек. не по-малко от:	15	... 35...
4. Съдържание на нелетливи вещества в % не по-малко от:	50	... 64.4
5. Съхливост до степен 4 при 20°C /в часа/ не повече от	2	... 2.....
6. Съдържание на органични вещества % не по-малко от:	12.5	...13.5...
7. Покривност, гр/м <sup>2</sup> не повече от:	200	...200
8. Външен вид на филма.	Равен ,по еталон	отговаря
9. Адхезия на филма , бала не повече от:	2	2.
10. Устойчивост на филма на дестили- рана вода при 20°C в часове не по-малко от:	15	отговаря ..
11. Светлоустойчивост, часове не по-малко от:	16	отговаря
12. Дълготрайност , изразена чрез устойчивост на ускорено стареене в цикли не по-малко от:	35	отоговаря

- And certificate of compliance.

All government owned furniture to be well covered and protected from the paint, also to be protected all floors, windows, doors, electrical switches and outlets, light fixtures and space heaters and all other materials, cabinets, inbuilt wardrobes , bathroom accessories or appliances that do not require painting. After finishing the work thorough of the house is required, removing all trash, construction materials, painted outlets and switches. Cleaning of the bathrooms and windows is not required.

5. Replace the floor tiles at the locations where the heating pipes have to be changed. The new tiles to be the same in color, size, quality as the existing. The total area is 30 sq.m.
6. Repair by replacement of the floor drain in the guest bathroom and laundry room on the first floor;
  - Remove the existing floor tiles around the existing floor drain, aprox. 4 sq.m.
  - Remove the old floor drains;
  - Install two new floor drains with P-trap, recommended brand VIEGA;
  - Install new floor tiles 4 sq.m., the new tiles to be the same in color, size and quality as the existing.
7. Fix the gap between the house wall and the walkway around the house by making washboard around the house.
8. Paint all grills on windows and patio doors.
9. Relocate the electrical switch of the guest bathroom on the 2<sup>nd</sup> floor.
10. Repair the stairs and the walk ways around the house.