

**CDC Kisumu- SOW – Cable management – Conference Rooms (Asembo and Banda)**

CDC would like to procure a complete Video Conferencing unit for use at CDC Offices in Kisumu, KEMRI Complex

<b>Requirements:</b>	<b>Vendor Response</b>
Site Visit is required: POC:- 1. Amos Odero (0728608676)	
<b>CRC Banda - Kisumu</b>	
<ul style="list-style-type: none"> <li>• The prospective contractor will be expected to provide neat cabling for the VC equipment. This includes electrical power and network connections. The microphones should be neatly placed. All cabling must be in appropriate trunking, hidden and neatly done. All physical works required to achieve such a setup must be catered for.</li> <li>• The contractor will be required to neaten any associated power cables, and where needed, run power cabling through separate trunking/duct from the data/video cables.</li> </ul>	
<b>Asembo Room - Kisian</b>	
<b>Requirement</b>	<b>Vendor response</b>
Neatening of VC cabling <ul style="list-style-type: none"> <li>• The contractor will be expected to neaten all cable running between the mounted equipment and the conference table – preferably by the use of floor trunking. Providing a DVI cable of sufficient length and a DVI to HDMI converter.</li> <li>• The contractor will be required to neaten any associated power cables, and where needed, run power cabling through separate trunking/duct from the data/video cables.</li> </ul>	
<b>Nyanza Conference Room - Kisian</b>	
<ul style="list-style-type: none"> <li>• The contractor will be required to connect the ceiling-mounted projector to the docking-station by:                             <ul style="list-style-type: none"> <li>○ Providing HDMI cable of sufficient length to run from the projector through the ceiling, down one wall onto the docking station. Providing an HDMI to VGA converter.</li> <li>○ Providing suitable wall and floor trunking for the above.</li> </ul> </li> </ul>	